Papa Pasta Concept Store in Central Kitchen — Builder Brief

2nd floor, Bedfordview · Rev C · 12 Nov 2026 · Read with drawing 01 (A0 at 1:25)

For pricing and site checks only, not for construction. Every dimension was scaled from the drawings below. Site-measure before anything is ordered or built.

1. Drawings in this pack

No.	File	What it is
01	01-PP-Central-Kitchen-Layout-RevC-A0-1to25.pdf	Final layout: store, cooking line, wet-services route, extract routes, clearances, equipment schedule
02	02-PP-Central-Kitchen-Layout-RevC-plan.png	Plan close-up of drawing 01 (for phone or email)
03	03-PP-Central-Kitchen-Builder-Brief-RevC.pdf (this document)	Scope, services and items to confirm
04	04-PP-Central-Kitchen-Layout-RevC.svg	Editable vector version of drawing 01
R1	Reference/Ventura-VEN41-SK2-Central-Kitchen.pdf	Base plan by Ventura (1:50, A0), the source of every room and equipment position
R2	Reference/Papa-Pasta-Concept-Store-2D-Plan.pdf	Store fit-out plan (layout unchanged, except the BOH change in item 2.6)
R3	Reference/ACDC-Lighting-Plan-Ryan-Hockley.pdf	Lighting layout for the store

2. Layout

1. **Store:** 5.00 × 8.00 m clear (40 m²), shopfront onto the south corridor. Its east wall is the existing wash-up partition.
2. **Cooking line:** one 5.63 m run on the store's north wall, facing north. From west to east: 1/2 table, 3 induction, 6 table, 5 and 4 tilt pans, 7 combi. All the wet and hot units are at the east end.
3. **Canopy:** 4.2 m long, over items 3 to 7 only. Ventura's drawing had 5.6 m.
4. **Blast chiller and hand basin:** blast chiller 12 at the hall's west end, hand basin 11 in the NW corner by the west door.
5. **Packaging line:** items 8 to 10 along the store's west wall, in the passage (2.58 m wide).
6. **Store back-of-house:** mirrored from the Papa Pasta plan. The double sink goes on the east (wash-up) wall, and storage and fridges go on the west. The low storage unit is 0.79 m long so the 0.78 m staff doorway stays clear.
7. **Unchanged:** prep, wash-up, lockers, coldroom, freezer, dry store and the training room.

Workflow (one direction): prep (east) → tilt pans and combi → along the 1.52 m aisle → blast chiller → packaging → dispatch through the west door. Dirty returns go east to wash-up, so clean and dirty routes never cross.

3. Builder scope to price

Trade	Item
Partitions	Store west wall, 8.0 m, 100 mm. Store north wall, 5.0 m, **fire-rated and insulated** (the hot line backs onto it). Infill partition, about 1.3 m, between the store's NE corner and the wash-up wall.
Shopfront	Aluminium shopfront to the south corridor, glazed for about 3.5 m (0.75 m to 4.25 m from the store's west wall), as on R2.
Optional	Walls and a double door between the passage and the lift lobby, to keep the public out of the kitchen.

Plumbing and drainage	One **wet-services spine** along the east partition. It serves the combi (water and drain), both tilt pans (water) and the store BOH double sink, then joins the wash-up sinks and grease trap 17. A floor channel and gully, about 2.9 m, runs in front of the tilt pans and combi and drains into the same spine. A small waste at the hall's west end serves hand basin 11 and the chiller condensate.
Gas	Supply to tilt pans 4 and 5 and the combi, all at the east end of the line.
Extraction	Canopy 4.2 m with its collar at the east end. Duct about 2.5 m north in the ceiling to the **solid façade section, which has no windows**. The store hood duct runs about 8 m north in the ceiling along the east partition to the same façade zone. Make-up air for both.
Electrical	Induction 3, combi, blast chiller, vacuum packer 9, and the store equipment on R2. Store lighting as on R3.

4. Clearances

Hall walkway in front of the cooking line: 1.52 m. Passage clear in front of the packaging line: 1.93 m. Opening from the hall into the passage: 2.05 m. Nothing stands on the north wall opposite the line, so the 1.52 m holds for its full length.

5. Equipment schedule (Ventura numbers)

Item	Equipment	Position
1/2	1650 SB table, 1200 shelf over	Line, west end, outside the canopy
3	Induction	Line, under the canopy
6	650 SB table	Line, landing table for the pans
4, 5	95 L gas tilting pans × 2	Line, east end, over the floor channel
7	6-pan GN 1/1 gas combi	Line, east end, on the wet spine
8, 10	1650 plain-top tables × 2	Passage, along the store's west wall
9	VPS0400 vacuum packer	Between 8 and 10
11	SS hand basin	Hall NW corner, by the west door
12	16-tray blast chiller	Hall, west end
13, 14	Mobile GN racks	Prep area (unchanged)
15–25	Wash-up and prep	Unchanged

6. Confirm on site before ordering

1. Drain stack positions and the slab build-up: confirm the route for the wet spine and floor channel to the stack.
2. Façade: the duct penetration in the solid section needs landlord or body-corporate approval.
3. Gas route to the east end of the line. Size the extract and make-up air.
4. Fire rating of the store north wall. Escape route through the west door and the passage.
5. The blast chiller stands in front of the 0.9 m west window. Confirm this is acceptable, or blank off that pane.
6. Ceiling height (needed for Ryan's lighting calculation and the duct route).
7. Every dimension: site-measure before anything is ordered.